
DUDEK



Tijuana River Sediment Management Work Plan IBWC Citizens Forum

City of Imperial Beach








Agenda

- 1 Project Overview
- 2 Sediment Management Work Plan
- Water and Sediment
 Characterization Monitoring
- 4 Next Steps

Project Overview

Planning effort to support long-term sediment management activities.


- Sediment Management Work Plan
- Water Quality and Sediment Monitoring Program




Sediment Management Work Plan

PURPOSE:

Develop sediment management processes to handle and beneficially reuse sediment captured in the Valley



Tijuana River Valley Stakeholders and Sediment Source Areas



Source Name	Ownership	Estimated Quantity
Goat Canyon	SINCE 1864	Annual 25,000-60,000 cy
Smuggler's Gulch & Pilot Channel	The City of SAN DIEGO	Annual Smuggler's Gulch: 50,000-100,000 cy Pilot Channel: 10,000-30,000 cy
Tijuana River Main Channel		Existing 1,000,000 cy Annual 60,000 cy
Brown Area Fill		One-time Removal 16,000-35,000 cy
Tijuana Estuary	FISH & WILDLIFE SERVICE	Project-based ~500,000 cy













Sediment Management Options

Category	Alternatives
	Beach and Nearshore Nourishment
	Thin-Layer Sediment Addition
Beneficial	Levee Rehabilitation
Re-use	Construction Material
Ne-use	Engineered Cap
	Mine Reclamation
	Open Ocean Dredged Material
Disposal	Disposal
	Confined Aquatic Disposal
	Upland Land Fill Disposal











Sediment Management Options

Category	Alternatives
	Beach and Nearshore Nourishment
	Thin-Layer Sediment Addition
Beneficial	Levee Rehabilitation
Re-use	Construction Material
NC-use	Engineered Cap
	Mine Reclamation
	Open Ocean Dredged Material
Disposal	Disposal
	Confined Aquatic Disposal
	Upland Land Fill Disposal





Sediment Management Basins in Mexico



Sediment Basin Name	capacity CY
Aguaje de la Tuna #1	2,930
Aguaje de la Tuna #2	3,060
Aguaje de la Tuna #3	13,340
Aguaje de la Tuna #4	10,590
Altamira	1,110
Arboledas	390
Camino Verde #1	4,710
Camino Verde #2	2,350
Camino Verde #3	6,280
Cañon Azteca	1,310
Cañon del Pato	4,710
Carlota Sosa	260

Sediment Basin Name	capacity CY
El Florido #1	5,490
El Florido #2	8,110
González Bocanegra	2,620
Jonhsito	4,190
Jonhson	7,190
Mexico Lindo #1	5,100
Mexico Lindo #2	3,920
Murua - Central Camionera	200
Pastejé-Aviación	2,960
Sánchez Taboada	5,230
Santa Fe	390
Volcán de Toluca	1,310

3

Sediment Management Work Plan- Monitoring Program

- · Water Quality Characterization Monitoring (7 sites)
 - 2 Wet Weather Sampling Events (1 completed)
 - 2 Dry Weather Sampling Events (1 completed)
- Sediment Characterization Monitoring (5 sites)
 - 2 Dry Weather Sampling Events (1 completed)
- Trash Evaluations (7 sites)
 - Conducted Simultaneously with Sediment Characterization
- Drone-assisted Trash Monitoring

Water Quality Characterization Monitoring Locations





Wet Weather Monitoring Results

March 10, 2021 - 0.56 inches of rain

Location	TSS (mg/L)	Fecal Coliform (MPN/100mL)
Yogurt Canyon	28	>1,600,000
Goat Canyon	3,820	>1,600,000
Smuggler's Gulch	262	>1,600,000
Silva's Drain	128	300,000
Canyon Del Sol	204	>1,600,000
Stewarts Drain	1,060	>1,600,000
Tijuana Main River	832	>1,600,000










Dry Weather Monitoring Results

June 23, 2021

Location	TSS (mg/L)	Fecal Coliform (MPN/100mL)
Yogurt Canyon	148	240,000
Goat Canyon	11,500	>1,600,000°
Smuggler's Gulch	199	<2,000
Silva's Drain	160	900,000
Canyon Del Sol	2,700	>1,600,000
Stewarts Drain	272	240,000
Tijuana Main River	22	800

[•] Exceeds reporting limit







Sediment Characterization Monitoring Locations





Sediment Characterization

- October 21, 2021- (Event 1)
 - 3 cores composited from each sediment source area
 - Comprehensive suite of analytes
 - CCR Title 22
 - · SCOUP
 - Inland Testing Manual
 - Analytical results pending



Trash Evaluation Preliminary Results

Location	Trash Score
Brown Fill	1
Flood Control Channel	11
Goat Canyon Sediment Basins	2
Potential Basin(s)- Main Tijuana River	1
Potential Basin(s)- Smuggler's Gulch	7
Smuggler's Gulch/Pilot Channel	5
Tijuana Estuary Tidal Restoration Project	







Trash Evaluation Drone Surveys

- Preliminary assessment-January 30th, 2021
- Evaluated drone-based trash monitoring with field methods
- Collaboration with 4Walls International







Drone imagery courtesy of 4 Walls International www.4wallsintl.com
@4wallsintl

Trash Evaluation Drone Surveys






Drone imagery courtesy of:
4 Walls International
www.4wallsintl.com
@4wallsintl

4

Next Steps- Connecting it Together



Key Takeaways



Sediment Management Framework Provides for Operational Efficiency

- Long-term Operations and Maintenance Planning
- Costs
- Regulatory Permitting Guidance

Cross-border Discharges Impact Water & Sediment Quality

- · Trash and Plastics
- · Fecal Indicator Bacteria
- Turbidity/CBOD

Stakeholder Collaboration Necessary

- Local Stakeholder Partnerships
- Improved Project Delivery
- Federal Contribution



BRYN EVANS - SENIOR PROJECT MANAGER – DUDEK

bevans@dudek.com

DYLAN CAWTHORNE - TECHNICAL PROFESSIONAL - WOOD

dylan.cawthorne@woodplc.com